

CmDv RFQ #2004

#2004.01 – Abatement Contractor Services Addendum #1 published 7/8/20

The following are revisions to the original bid packet:

1. Page 2 (Scope of Work): DELETE item #4 entirely since air monitoring is not required by EPA:
~~AIR MONITORING: clearance air monitoring shall be performed and clearance sampling provided. A minimum of 4 Phase Contrast Microscopy (PCM) ambient air samples shall be collected at the perimeter of the work area. All air monitoring shall be performed by a Louisiana accredited contractor/supervisor and analyzed using PCM in accordance with the National Institute for Occupational Safety and Health's (NIOSH) 7400 Analytical Method by persons with NIOSH 582 equivalent training and proficient per an American Industrial Hygiene Association (AIHA) Proficiency Analytical Testing (PAT) Program.~~
2. Page 13 (Contractor Fee Schedule): REPLACE entire page with attached.
 - a. Item #2 related to air monitoring has been deleted. Subsequent items have been renumbered.
 - b. New Item #3 – remove “ & Debris” at the end of the item description.
 - c. Estimated Quantities have been added to each line item to provide an extended price.

All other information in the original bid packet is applicable. Should you have questions, please contact the Administrator at 318-449-5070 or email cda@cityofalex.com.

Addendum Number #2004.01 has been noted on the revised
Contractor Fee Schedule page.

RFQ #2004.01 Attachment #2 – Contractor Fee Schedule

Task #	Work Description	Unit Price	Per	Est. Qty.*	Extended Price
1	Wet all demolition activity	included			
2*	RACM Demolition & Disposal		sf	5,000	
3*	Abate & Dispose of Pipe and Pipe Fitting Insulation		lf	400	
4	Abate & Dispose of Floor Tile & Mastic as ACM		sf	12,500	
5	Abate & Dispose of Sheet Flooring as ACM		sf	2,500	
6	Abate & Dispose of Window and Door Caulks and/or Glazing as ACM		lf	1,000	
7	Abate & Dispose of Carpet & Mastic as ACM		sf	500	
8	Abate & Dispose of Asphaltic Roofing Materials as ACM		sf	3,000	
9	Abate & Dispose of Drywall & Joint Compound		sf	1,500	
10	Abate & Dispose of Surfacing Materials as ACM, including plaster substrate, drywall wall & ceiling texture		sf	5,000	
11	Abate & Dispose of Ceiling Tile as ACM		sf	1,000	
12	Abate & Dispose of Transite Siding, Roofing, soffit and fascia, including on Exempted Structures		sf	20,000	
13	Three (3) Day Emergency Additional Fee		each	5	
14	Mobilization and/or Demobilization Fee		each	10	
TOTAL					

- Fee Schedules without completed signature / company information will automatically be rejected. All information must be completed in ink. Signature must be hand written. Electronic or stamped signatures will be considered non-responsive and will be rejected. All information requested below must be in legible print, with the exception of the Authorized Signature.
- Work Description details shall be found in Section II of this document.
- This RFQ does not represent a City public or urban project and is not part of a larger construction public project. These are *Nuisance Abatement Demolitions*.
- Line items with an (*) by the Task # has been changed from the original RFQ document. In addition, estimated quantities have been added to calculate Extended Price Total.

ADDENDUM NUMBER(S) ACKNOWLEDGED, IF APPLICABLE: #2004.01 (7/13/2020)

COMPANY NAME _____ DATE _____

STREET ADDRESS _____ P O BOX _____

CITY _____ STATE _____ ZIP _____

TELEPHONE NUMBER _____ DUNS NUMBER _____

AUTHORIZED SIGNATURE: _____