

CmDv RFQ #2003

#2003.01 –Demolition Contractor Services Addendum #1 published 7/2/20

The following are revisions to the original bid packet:

1. Page 3 (Scope of Work): ADD new item #19:
DEMOLISH and DISPOSE of ALL IDENTIFIED SLAB ON-GRADE STRUCTURES / **SLAB TO REMAIN IN PLACE:**
demolish all parts of any structure identified onsite at, **above the concrete slab**, including wall assemblies (possibly with brick veneer), roof assemblies, multiple story assemblies, accessory structures, steps/stairs, piping, wiring, plumbing, mechanical and other materials, visible before and/or after demolition activity is complete, which are attached to or part of the structure. Load, haul and dump all debris at the appropriate landfill. This shall include any structure debris, structure contents, trash / garbage, white goods, appliances, HVAC units and incidental vegetation but does not include trees or tires. **Concrete slab and footings to remain in place, in tack and not removed.** Grading and backfill may be required.
 - a. If a concrete structure slab is left in place, any potential asbestos containing tile must be removed from the slab surface, however, the mastic can remain.
2. Page 12 (Contractor Fee Schedule): REPLACE entire page with attached.

All other information in the original bid packet is applicable. Should you have questions, please contact the Administrator at 318-449-5070 or email cda@cityofalex.com.

**Addendum Number #2003.01 has been noted on the revised
Contractor Fee Schedule page.**

RFQ #2003.01 Attachment #2 – Contractor Fee Schedule

Task #	Work Description	Price	Method
1	Wet all demolition activity	included	
2	Demolish & Dispose Pier and Beam Raised Structures		sf
3	Demolish & Dispose Slab On-Grade Structures		sf
4	Demolish & Dispose Mobile Home Structures		sf
5	Demolish & Dispose Slabs		sf
6	Demolish & Dispose Fencing		lf
7	Demolish & Dispose Swimming Pool and/or Water Features		each
8	Demolish & Dispose Tanks, Traps, Basins and/or Drains		each
9	Demolish / Remove ONLY All Structures, Trees, Fencing, Swimming Pools, Tires, etc. DISPOSAL BY CITY.		day rate
10	Remove Trees		each
11	Relocate Tires	included	
12	Recover HVAC Refrigerant		each
13	Provide & Spread Clean Fill Dirt		yd
14	Provide Seed and Hay Lot Stabilization		each
15	Provide Mowed Lot		each
16	Three (3) Day Emergency Additional Fee		each
17	Ten (10) Day Expedited Additional Fee		each
18	Restricted Access Additional Fee		each
19	Demolish & Dispose Slab On-Grade Structures / Slab to remain		sf

1. Fee Schedules without completed signature / company information will automatically be rejected. All information must be completed in ink. Signature must be hand written. Electronic or stamped signatures will be considered non-responsive and will be rejected. All information requested below must be in legible print, with the exception of the Authorized Signature.
2. Work Description details shall be found in Section II of this document.
3. This RFQ does not represent a City public or urban project and is not part of a larger construction public project. These are *Nuisance Abatement Demolitions*.

ADDENDUM NUMBER(S) ACKNOWLEDGED, IF APPLICABLE: #2003.01

COMPANY NAME _____ DATE _____

STREET ADDRESS _____ P O BOX _____

CITY _____ STATE _____ ZIP _____

TELEPHONE NUMBER _____ DUNS NUMBER _____

AUTHORIZED SIGNATURE: _____